

Lincolnshire County Council Section 19 Investigations - Network North Area G - Contact Officer Alan Brown - Area Highways Manager						Identified Actions/Works				
Date of Incident	Town & Location	Description of Flooding	Risk Management Authorities with Responsibilities and whether they are exercising functions	Actions and Recommendations	Consideration for inclusion in future Common Works Programme	Proposed Action/Works	Promoter	Status	Estimated Timescales Recommendation Scheme Completion	S19 Report File Reference
10/07/2012 Page 43	Bardney Laing Close	Surcharging from foul and surface water sewers due to blockages within the surface water system. Concerns over operation of foul sewer system due to possible downstream pump failure, excessive surface water connectivity to the foul sewer and the effectiveness of the overflow arrangements at the pumping station. 1 Property	LCC - Yes Anglian Water- Yes Witham 3rd IDB - Yes	LCC system checked and functioning effectively. Anglian Water has provided resilience measures at a property on Laing Road. Anglian Water to check and repair their systems and investigate the flow carried by the foul system and validate the capacity of the foul sewer, including the operational effectiveness of the foul pumping station and its emergency overflow arrangements. The installation of a flap valve to the surface water sewer outfall at the rear of Baltholomew Close should be investigated. Witham 3rd Internal Drainage Board to complete its study into the benefits of upgrading its culvert through the garden of a property on Abbey Road.	Yes- possible upgrading of Witham 3rd culvert.	LCC system checked and ok, problems found with AW surface water system and reported to AW, mitigating action taken by erecting flood boards at the property. AW has confirmed all remedial work has been carried out, and a regular maintenance regime is now in place. Witham 3rd IDB have installed a new culvert under Abbey Road to increase capacity of the drainage system. This work was carried out in November 2014.	LCC AW Witham 3rd IDB	Complete	Complete Winter 2014	S19-037
23/12/2012	Heighington High Street	Surface water and ground water flooding (from private well) entered the lowest room in the property (the former dairy) following prolonged wet weather.	LCC - Yes	The provision of a new overflow for the well will allow for a significant discharge from the area. However, it is difficult to confirm whether the arrangements installed will limit the rise in groundwater levels should similar weather conditions reoccur. The effectiveness of the completed installation should be monitored by on-going liaison between LLFA and the owners.	No	The property owners have subsequently obtained consent to lay a new overflow pipe from the well to the beck and have privately funded its construction with all the site works complete.	Riparian Owner	Complete	Complete Spring 2014	S19-038

This page is intentionally left blank